

# CERTIFICATE OF LOCATION OF GOVERNMENT CORNER

NORTHEAST Corner of Section 1, Township 106, Range 40, 5TH P.M.

STATE OF MINNESOTA, County of MURRAY


At the corner location shown on the sketch:

On 07-11-2011 found a bent iron.  
DATE

left monument as found,  lowered monument,  removed monument (explain)

On 07-11-2011 placed a 1" pipe with seal #43844.  
DATE

### SKETCH OF REFERENCE TIES




Minnesota State Plane Coordinate System Murray County Datum NAD83 (1996)

N: 163448.678  
E: 548389.332

Nail and bottle cap in pedestal guard post SE 39.25'  
Nail and seal in utility pole West 32.00'

Statement of evidence relative to this corner location is on back of page.

I hereby certify that this document and the data contained herein was prepared by me or under my direct supervision.

  
SIGNATURE 1/23/12  
DATE

Registration No. 43844

Land Surveyor,  Professional Engineer  
 County Surveyor,  County Engineer

OFFICE OF THE COUNTY RECORDER  
County of

I hereby certify that this document was filed in the Co. Recorders office at \_\_\_\_\_ .M on the \_\_\_\_\_ day of JAN 25 2012 A.D. 20 \_\_\_\_\_

County Recorder James V. Johnson  
By \_\_\_\_\_, Deputy

DOCUMENT NO. \_\_\_\_\_

## Statement of Evidence

In 1861, J. W. Myers did the original survey of the township lines.

On October 15, 1907, J. W. Woolstencraft measured the east line. He did not record a monument at the corner.

On December 29, 1989, the Murray County Highway Department recorded a white stone at the corner.

On July 11, 2011, Bueltel-Moseng Land Surveying found a bent iron at the corner. We removed the iron and probed for the stone. We did not find the stone. We used the ties from 1989 to reset the corner, it fell in the same spot as the bent iron. We set a 1" pipe with seal #43844 in place of the bent iron.